Machine seam roof, Kindergarten 900 m² | Helsinki



Description

Niitty, a kindergarten in the city of Helsinki, was coated with ElaProof S according to the manufacturer's instructions twice. This ensured a minimum dry film thickness of 0.6 mm in terms of waterproofing.

Information

In connection with the coating work, the holes caused by removing the old snow barriers were patched with ElaProof H and Base fabric. In addition, the vertical seams of the long miters were treated in the same way. The ventilation of the roof was improved with vacuum fans hand-made by a sheet metal worker. After the coating work new snow barriers, roof bridges and ladders were installed.

Project information

Client: City of Helsinki, Kindergarten Niitty
Project: Kindergarten Niitty
Address: Laurinmäenpolku 4, Helsinki, Finland
Material: Machine seam roof
Contractor: JJ-Kattohuolto Oy
Time and city: 08/2021 | Helsinki

Products used in the project

- ElaProof PRO S
- ElaProof Classic H
- ElaProof Base Fabric







